

DETAILED BREAKDOWN OF ITEMS

Prepared for: Division Avenue Ne
 Project ID: Division Avenue Ne Washington, DC 20019, Lots 52,53,54,55,56 & 57 Square 5203
 Scope: Site Work

PARAMETRIC
 ESTIMATES 
 Let's Win This Bid Together! Your Vision, Our Commitment

Date: 1-Aug-22

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS									
1	Permits	LS	1	0%	1	\$ -	\$ -	\$ 5,000.00	\$ 5,000.00
2	Supervision and Coordination	LS	1	0%	1	\$ -	\$ -	\$ 20,000.00	\$ 20,000.00
3	Submittals and Shop drawings	LS	1	0%	1	\$ -	\$ -	\$ 2,500.00	\$ 2,500.00
4	Final Cleaning	LS	1	0%	1	\$ -	\$ -	\$ 2,500.00	\$ 2,500.00
5	Mobilization Costs	LS	1	0%	1	\$ -	\$ -	\$ 10,000.00	\$ 10,000.00
6	Temporary Control & Facilities	LS	1	0%	1	\$ -	\$ -	\$ 5,000.00	\$ 5,000.00
7	Scaffolding	SF	0	0%	0	\$ -	\$ -	\$ -	\$ -
SUBTOTAL									\$ 45,000
EXISTING CONDITION									
DEMOLITION									
8	Remove 6' Chain Link Fence and Gate Incl. Fence Post & Post Footing	LF	142	0%	142	\$ -	\$ -	\$ 25.00	\$ 3,557.00
9	Remove 6' Iron Fence Incl. Fence Post & Post Footing	LF	327	0%	327	\$ 25.00	\$ -	\$ 25.00	\$ 8,171.00
10	Remove Steel Fence Incl. Fence Post & Post Footing	LF	121	0%	121	\$ 25.00	\$ -	\$ 25.00	\$ 3,027.50
11	Remove Asphalt Pavement	SF	1500	0%	1500	\$ -	\$ -	\$ 12.00	\$ 18,000.00
12	Remove Concrete Apron / Sidewalk down to subgrade	SF	798	0%	798	10.00	\$ -	\$ 10.00	\$ 7,980.00
13	Remove Concrete Curb	LF	115.00	0%	115	\$ 10.00	\$ -	\$ 10.00	\$ 1,150.00
14	Remove Concrete Footers Note: 3.5' High assume Please Confirm	CY	136	0%	136	\$ 120.00	\$ -	\$ 120.00	\$ 16,320.00
15	Remove Footers Excavation Note: 3.5' High assume Please Confirm	CY	222	0%	222	\$ 70.00	\$ -	\$ 70.00	\$ 15,540.00
16	Remove Overhead Utility & Pole	LF	267	0%	267	10.00	\$ -	\$ 10.00	\$ 2,670.00
17	Abandonment Water, Sewer & Gas Services (For Location 4 LOC) Note: Follow Utility Company Standards to Abandon	LS	1	0%	1	\$ 8,000.00	\$ -	\$ 8,000.00	\$ 8,000.00
SUBTOTAL									\$ 84,416
EARTHWORK									
EXCAVATION									
18	6" PVC Excavation @ 3' W	CY	974	10%	1071	\$ 65.00	\$ -	\$ 65.00	\$ 69,641.00
19	8" SD (PVC) Excavation @ 3' W	CY	675	10%	743	\$ 65.00	\$ -	\$ 65.00	\$ 48,262.50
20	10" SD (PVC) Excavation @ 3' W	CY	575	10%	633	\$ 65.00	\$ -	\$ 65.00	\$ 41,112.50
21	15" RCPC Excavation @ 3' W	CY	907	10%	998	\$ 65.00	\$ -	\$ 65.00	\$ 64,850.50
22	Excavation for Precast Manhole	CY	0	10%	0	\$ 65.00	\$ -	\$ 65.00	\$ -
BACK FILL									
23	6" PVC Back fill @ 3' W	CY	1070	10%	1070	\$ 55.00	\$ -	\$ 55.00	\$ 58,866.50
24	8" SD (PVC) Back fill @ 3' W	CY	741	10%	741	\$ 55.00	\$ -	\$ 55.00	\$ 40,777.00
25	10" SD (PVC) Back fill @ 3' W	CY	631	10%	631	\$ 55.00	\$ -	\$ 55.00	\$ 34,727.00
26	15" RCPC Back fill @ 3' W	CY	997	10%	997	\$ 55.00	\$ -	\$ 55.00	\$ 54,813.00
SUBTOTAL									\$ 413,050
SITE IMPROVEMENTS									
CONCRETE DRIVEWAY									
27	7" D Concrete Driveway w/ Wire Fabric Reinforcement @ Entrance	SF	152	10%	167	\$ 8.00	\$ 12.00	\$ 20.00	\$ 3,344.00
PERMEABLE PAVER DRIVEWAY									
28	Permeable Paver Driveway Note: Portion of Drive way by Others VIF	SF	2970	10%	3267	\$ 7.00	\$ 8.00	\$ 15.00	\$ 49,005.00
PERMEABLE PAVER									
29	6" Permeable Pavers	SF	2148	10%	2363	\$ 5.00	\$ 6.00	\$ 11.00	\$ 25,989.11
30	2" Bedding Layer (#8 Stone)	SF	2148	10%	2363	\$ 2.85	\$ 3.00	\$ 5.85	\$ 13,822.38
31	12" Bedding Layer (#2 Stone)	SF	2148	10%	2363	\$ 6.00	\$ 8.00	\$ 14.00	\$ 33,079.20
32	4" Bedding Layer (#8 Stone)	SF	2148	10%	2363	\$ 4.00	\$ 6.00	\$ 10.00	\$ 23,628.00
33	Filter Fabric Below Stone	SF	2148	10%	2363	\$ 0.80	\$ 0.50	\$ 1.30	\$ 3,071.64
34	Geotextile Fabric	SF	700	10%	770	\$ 0.80	\$ 0.47	\$ 1.27	\$ 977.90
PERMEABLE PAVER SIDEWALK									
35	Permeable Pavement Pedestrian Walk (Sheet No. CIV210)	SF	1227	10%	1350	\$ 14.00	\$ 16.00	\$ 30.00	\$ 40,503.54
36	Bedding Layer Aashto #8	SF	1227	10%	1350	\$ 5.00	\$ 6.00	\$ 11.00	\$ 14,851.30
37	Double Washed Aggregate into #8	SF	1227	10%	1350	\$ 7.00	\$ 8.00	\$ 15.00	\$ 20,251.77
38	4"x7-1/2" Concrete Edge Retention	SF	1227	10%	1350	\$ 4.00	\$ 5.00	\$ 9.00	\$ 12,151.06
CONCRETE SIDEWALK									
39	Concrete Pad for Tray Up	SF	61	10%	67	\$ 8.00	\$ 12.00	\$ 20.00	\$ 1,342.00
CONCRETE SIDEWALK									
40	4" D Concrete Pedestrian	SF	1060	10%	1166	\$ 14.00	\$ 16.00	\$ 30.00	\$ 34,980.00
41	4" D Graded Aggregate Base	SF	1060	10%	1166	\$ 7.00	\$ 8.00	\$ 15.00	\$ 17,490.00
CONCRETE STRIP									
42	6" Pea Gravel Strip	LF	165	10%	182	\$ 3.85	\$ 4.00	\$ 7.85	\$ 1,424.78
CONCRETE STRIP ON BIOSWALE									
43	Concrete Strip	SF	1265	10%	1392	\$ 8.00	\$ 12.00	\$ 20.00	\$ 27,830.00
44	Concrete Wall around Bioretention/Bioswale	CY	17	10%	19	\$ 680.00	\$ 750.00	\$ 1,430.00	\$ 26,741.00

DETAILED BREAKDOWN OF ITEMS

Prepared for: Division Avenue Ne
 Project ID: Division Avenue Ne Washington, DC 20019, Lots 52,53,54,55,56 & 57 Square 5203
 Scope: Site Work



Let's Win This Bid Together! Your Vision, Our Commitment

Date: 1-Aug-22

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
SUBTOTAL \$									350,483
UTILITIES									
PVC PIPES									
45	4" Perforated Storm Pipe (PVC)	LF	151	10%	166	\$ 2.25	\$ 1.19	\$ 3.44	\$ 570.85
46	4" Sanitary Sewer (PVC)	LF	217	10%	238	\$ 2.25	\$ 1.19	\$ 3.44	\$ 819.43
47	4" SCH40 PVC Sanitary Sewer Lateral (2% Min. Slope)	LF	35	10%	38	\$ 2.25	\$ 1.58	\$ 3.83	\$ 147.37
48	4" SCH40 Perforated PVC Underdrain Bioswale-B SWM ID: 6006-1-1	LF	153	10%	168	\$ 2.75	\$ 1.88	\$ 4.63	\$ 778.21
49	4" SCH40 Perforated PVC Underdrain Bioswale-B SWM ID: 6006-1-3	LF	151	10%	166	\$ 2.75	\$ 1.88	\$ 4.63	\$ 768.69
50	6" Sanitary Sewer (PVC) SCH40 PVC Sanitary Sewer	LF	183	10%	201	\$ 10.00	\$ 45.00	\$ 55.00	\$ 11,051.54
STORM SEWER PIPES									
51	8" Storm Sewer (SD)	LF	145	10%	159	\$ 10.00	\$ 1.00	\$ 65.00	\$ 10,357.49
52	10" Storm Sewer (SD)	LF	46	10%	51	\$ 12.00	\$ 1.00	\$ 77.00	\$ 3,937.70
TYPE K COPPER PIPE									
53	1" Type K Copper Domestic Service	LF	59	10%	65	\$ 11.56	\$ 11.56	\$ 16.56	\$ 1,075.11
54	2" Type K Copper Fire Service	LF	135	10%	149	\$ 28.01	\$ 28.01	\$ 36.01	\$ 5,358.18
55	2" Type K Copper Domestic Water Service	LF	174	10%	191	\$ 28.01	\$ 28.01	\$ 36.01	\$ 6,875.68
WATER METER									
56	Water Meter	EA	1	0%	1	\$ 1,230.00	\$ 1,230.00	\$ 1,730.00	\$ 1,730.00
PRECAST MANHOLE									
57	24" D Precast Concrete w/ Cover @ 9' H	EA	3	0%	3	\$ 588.00	\$ 588.00	\$ 838.00	\$ 2,514.00
VALVE									
58	1" Curb stop Valve	EA	6	0%	6	\$ 55.00	\$ 40.00	\$ 95.00	\$ 570.00
59	2" Curb stop Valve	EA	1	0%	1	\$ 60.00	\$ 78.00	\$ 138.00	\$ 138.00
CLEANOUT									
60	4" SCHO PVC Cleanout	EA	1	0%	1	\$ 85.00	\$ 25.62	\$ 110.62	\$ 110.62
61	Cleanout	EA	16	0%	16	\$ 85.00	\$ 25.62	\$ 110.62	\$ 1,769.92
CHECK DAM									
62	7'-7" W Check Dam	EA	8	0%	8	\$ 550.00	\$ 1,200.00	\$ 1,750.00	\$ 14,000.00
REINFORCED CONCRETE PIPE									
63	15" Reinforced Concrete Pipe (RCPR)	LF	90	10%	99	\$ 35.00	\$ 65.00	\$ 100.00	\$ 9,918.70
CHECK DAM									
64	Crown of Swale	EA	1	0%	1	\$ 600.00	\$ 400.00	\$ 1,000.00	\$ 1,000.00
SUBTOTAL \$									73,491
ELECTRICAL									
65	Allowance for electrical work Note: Plans do not shown any electrical work. We have added an allowance for this division. Please Confirm & VIF.	LS	1	0%	1	\$ 15,000.00	\$ -	\$ 15,000.00	\$ 15,000.00
SUBTOTAL \$									15,000

	PROJECTED COST			\$981,440
OVERHEAD AND PROFIT	0.1	0.1	10%	\$98,144
LABOR BURDEN	0	0	0%	\$0
Tax	0	0	0%	\$0
INSURANCE	0	0	0%	\$0
CONTINGENCY	0	0	0%	\$0
TOTAL TRADE COST				\$1,079,584

- Notes:
- 1 We have take building concrete footer demolition in site work. Please Confirm & VIF
 - 2 Landscaping is excluded in our take off. Please Confirm
 - 3 We have provided an allowance for electrical work Please VIF.